

## Findings

While the contamination levels of the soil are within acceptable limits, there is a high risk of contaminants being carried by surfacewater and groundwater into the Waingiri stream.

### To mitigate the potential risk of discharge we recommend:

1. Implement specialist controls during proposed land disturbance works via a CSMP
2. Remove significantly impacted soils within the construction envelope

### Consenting requirements:

1. It is highly likely that the development will require resource consent because the volume of soil disturbance will be over the permitted activity limit under Reg 9 of the NESCS.
2. The project will require a discharge consent. This is because the volume of soil disturbance (and other conditions) will likely be over the permitted activity limit under *both* the current GWRC xx and the proposed NRP bla bla.

### Notes:

- Under the GWRC XX this is considered a Controlled Activity
- Under the NRP XX this is considered a Discretionary Activity